Ankura Homes - The WOODS
Villa Specifications

Structure

- RCC Framed Isolated Foundations and RCC Framed Structure upto Columns.
- VPCC wall around Plinth to retain the compacted soil with in the Villa.

ATT

- Soil treatment with approved chemical (Chlorpyrifos 20% EC or equivalent) before Grade slab.
- Treatment carried out as per IS:6313 (Part 2) standards.

Roof

- Fabrication and Fixing of Reputed make of MS Pipes based on Approved design by Consultant.
- Fixing of Cement V Board 12mm sheets of Reputed make to cover the Entire Roof over structural framing.
- Laying Waterproofed Polypropylene sheet at all joints and over laps to keep the roof water tight.
- Fixing Reputed make of Cement Roof tiles with proper overlaps and corner joints including ridge caps to keep entire roof water tight.

Walls

- Outer Walls of 230mm thick with Karimnagar Red Bricks.
- Inner Walls of 100/200mm thick based on height of the walls with Karimnagar Red Bricks.
- DPC Shall be laid on slab level for better water proof barrier and Concrete beds on walls as required as per standards.

Plastering

- INTERNAL : Sponge Finished Single Coat Wall Plaster of 12-16mm thick with Natural River Sand.
- EXTERNAL : Sponge Finished Double Coat Wall Plaster of 18-20mm thick with Natural River Sand.

Water Proofing

- INTERNAL : Wet Areas vertical water proofing upto 2' height with reputed methodolgies.
- EXTERNAL : Wet Areas vertical water proofing upto 2' height with reputed methodolgies.

Painting

CEILING :	Pipes & V Board Joints filling with Crack Seal material of reputed make.
	Application of 2 Coats Putty + Primer + 2 Coats of Tractor Emulsion of Reputed make.
	Sanding and application of 1coat Zinc Primer + 2 Coats of White Paint Enamel to MS Members.
INTERNAL :	Application of 2 Coats Putty + Primer + 2 Coats of Internal Emulsion (White) of Reputed make.
EXTERNAL :	Application of 1-1.5mm Thick Synthetic Texture + 2 Coats of External Emulsion (White) of Reputed make.

Flooring

TOILETS :	Ceramic or Vitrified Wall tiles of Selected and Reputed Brand shall be fixed upto 7' height with edge chamfer.
	Ceramic or Vitrified Antiskid Floor tiles of Selected and Reputed Brand shall be fixed with Proper Slopes.
LIV/DIN/KIT :	800x 800 / 600 x 600 of Double Glazed Vitrified Tiles of Reputed Brand shall be fixed with 100mm skirting on walls.
KITCHEN :	Wall Tiles of Selected and Reputed brand shall be fixed upto 600mm height above Kitchen Platform.
UTILITY :	Wall Tiles of Selected and Reputed brand shall be fixed upto 1Mtr height from FFL.
BEDROOMS :	800x 800 / 600 x 600 of Double Glazed Vitrified Tiles of Reputed Brand shall be fixed with 100mm skirting on walls.
VERRANDAH :	Ceramic or Vitrified Antiskid Floor tiles of Selected and Reputed Brand shall be fixed with Proper Slopes.
NOTE :	2mm Spacer will be considered for all Floor Areas fillingwith Epoxy/Cement grouts based on requirement.

Doors

MAIN DOOR :	7-8' Height Factory made Solid Wood Frame with Veneer Finsihed flush shutter and PU Polish, fitted with reputed Hardware inlu
INTERNAL DOORS :	7' Height Factory made Solid Wood or Engineered wood Frame with Laminate flush shutter with reputed Hardware.
UTILITY/OUT DOOR :	7' Height Factory made Metal Frame and shutter with reputed Hardware.

Windows

SLIDING DOORS :	2.5 Track UPVC Sliding Doors with Plain Glass, fitted with necessary hardware and provision for Mosquito mesh.
WINDOWS :	2.5 Track UPVC Sliding/Openable Shutters with Plain Glass, fitted with necessary hardware and provision for Mosquito mesh.
VENTILATORS :	Aluminium / UPVC Ventilators with provision for Exhaust Fan

Kitchen / Utility

COUNTER TOP :	Black Granite of 18-20mm thick Counter top with polished edges.
SINK :	Stainless Steel, Under Mount Single/Double Bowl Sink based on selection shall fixed with required fittings

Plumbing

SANITARY :	Wall-hung/counter/under-counter wash basins; Western Water Closet (EWC) with dual-flush; reputed brands with fittings
CP FITTINGS :	Chrome-plated/brushed nickel or matte black; reputed brands for mixers, showers, taps including fittings.
PLUMBING :	CPVC supply lines; sewer/drainage with PVC/Foam Core Pipes; rainwater pipes as per regulations with all reputaed makes.
PROVISIONS :	Extra Provisions for Dishwasher, Washing Machine & Water Purifier.

Electrical

KITCHEN :	Power Outlets for Chimney, Hob/Ignition Stove, Oven, Mixer Grinder, Refrigerator & Water Purifier.
CONDUITS :	HMS PVC Conduits of required dia in all concealed walls with Metal Boxes of required sizes.
WIRING :	Concealed Copper Wiring FRLS of reputed make including DB Dressing with MCB of reputed make.
SWITCHES :	Modular Switches of Reputed make shall be provided.

External Development

PLUMBING :	HDPE/CPVC Inlet Lines from External lines to Sump with Water Meter provision.
	PVC/Foam Core Pipes with required Manholes for Soil and Waste Pipes to Soak Pit inside the plot.
	Pneumatic pumping to all fixtures from Sump with adequate pressure.
	Irrigation Lines with Drip & Sprinklers based on nature of Landscape/Plantation with proper routing.
	Roof Rain Water shall be routed to RWH pits provided inside the Villa.
ELECTRICAL :	Concealed Incoming Cables from Ext. lines with Meter fixing to Distribution Box.
	Electrical Provision for Gazibo shall be provided based on Customer Selection.
	EV Charging Provision shall be provided at Parking based on Customer Request.
	Provision for CCTV shall be Provided as per Customer Request.
LANDSCAPING :	Landscaped Gardens, Native Species Plants, Fruit Trees shall be provided based on customer selection.
	Walking Paths, Seating Areas, Design Fencing shall be placed as per Drawings.